Notification dated 14th February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 2nd March 1936 (2 P.M.) for constructing quarters for the Assistant Superintendent of Police, Provincial Reserve Police, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of July 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees four hundred only (Rs. 400) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing quarters for the Assistant Suerpintendent of Police, Provincial Reserve Police, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Transfer of works to third parties by selected contractors will not be countenanced by the department and in the case of any such attempt, the earnest money is liable to be forfeited at the discretion of the Executive Engineer.

Abstract estimate for constructing Assistant Superintendent's Quarters for the Reserve Police Lines in Mysore Road, Bangalore.

No.	Items of work	Unit	Rate	Quantity	Rate in figures	Rate in words
			Rs. a. p.			
1	Earthwork excavation and filling in basement, watering, tamping, etc., complete	C.yds.	0 4 0	243		
2	Lime mortar concrete in stone jelly ..	C.ft.	0 3 6	3,323		
3	Size stone in lime mortar, with bond stones 6 feet apart foundation and basement	C.ft.	0 4 6	3,618		
4	Burnt brick in clay superstructure ..	,,	0 3 3	3,961		
5	Burnt brick in lime mortar	,,	0 4 0	950		
6	Burnt stone slabs 6″ thick with exposed portions two line dressed ..	S.ft.	0 5 6	1,888		
7	Providing and fixing teak-wood doors with panelled shutters $1\frac{1}{4}$″ thick, frame $3\frac{1}{2}'\times4\frac{1}{2}'$ with iron fittings, clamps and paintings, etc., complete	,,	1 8 0	489		
8	Providing and fixing teak-wood windows frame $4'\times5'$ with glazed shutters $1\frac{1}{4}$″ thick, iron bars, vertical and cross bars, clamps, iron fittings and pointing, etc., complete.	S.ft.	1 10 0	411		

No.	Items of work	Unit	Rate	Quantity	Rate in figures	Rate in words
			Rs a. p.			
9	Providing and fixing teak-wood glazed ventilators with paintings, etc., complete	S.ft.	1 0 0	24		
10	Tata's tested girders with cutting, hoisting and painting, etc., complete.	cwt.	10 8 0	26·00		
11	Roofing with R.B.C. single course 7″ thick with necessary reinforcement 5″ apart and 3″ to 4″ surki concrete and two layers of flat tiles, in compositions mortar and plastered both sides	Sqr.	65 0 0	22·5		
12	Burnt brick in mortar low, plain parapet wall with plastering as per design	R.ft.	0 8 0	336		
13	Ornamental works	L. S.	Details	during execution		
14	Lime mortar plastering 2 coats with whitewashing 3 coats including moulding	Sqr.	3 8 0	77·27		
15	Cement pointing to basement with cut lines, etc.	,,	3 0 0	7·50		
16	T. W. Almirahs with planks and panelled shutters with painting, etc. complete	S.ft.	1 4 0	66		
17	Flooring with 1½″ thick cement concrete over 3″ lime mortar concrete and red cement plaster and finishing with damp proof course one foot thick (with boulders and sand, etc.) complete	Sqr.	30 0 0	18·7		
18	Boxing girders with terrace bricks in cement mortar and lime mortar finishing	R.ft.	0 8 0	69		
19	Finishing the edges of doors, windows with cement and plastering, etc., complete	R.ft.	..	..		
20	Line down water pipes 4″ dia. fixing, etc., complete	R.ft.	0 8 0	150		
21	Providing sinks in both rooms and flat farm in pantry	Details	during execution			

Notification dated 15th February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Buildings Division, up to 4th March 1936 (2 P.M), for constructing the Middle School and the Hostel for the Urdu Girls in Fort area, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Bangalore between the hours of 11 A.M. and 5 P.M.

3. Tender should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees one thousand and seven hundred only (Rs. 1,700) in cash or Government Promissory Notes, as earnest money, and be superscribed " Tender for constructing the Middle School and the Hostel for the Girls in Fort area, Bangalore," in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive and reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10 Rates for non-tendered and non-estimated items shall be as per schedule rates of the department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

13. Transfer of works to third parties by selected contractors will not be countenanced by the department and in case of any such attempts the earnest money is liable to be forfeited at the discretion of the Superintending Engineer.

Abstract estimate of quantities for constructing a Middle School and a Hostel for the Urdu Girls in the Fort area, Bangalore.

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
1	Earthwork excavation for foundation keeping the same at a distance and filling in the sides of the excavation and between the basement including watering, etc., complete	C.yds.	0 4 0	388	
2	Laying burnt stone jelly concrete in (1 : 2) lime and sand mortar including tamping, etc., complete	C.ft.	0 3 6	2,630	
3	Construct ng the foundation and basement and also the superstructure of only the exterior walls with size stone in (1 : 2) lime mortar	,,	0 5 0	10,121	
4	Constructing the superstructure of interior walls with burnt brick in chunam mortar (1 : 2)	,,	0 5 0	4,779	
5	Laying burnt stone slabs 6″ thick roughly dressed, including fixing in mortar in bed joint and with asphalt in vertical joints etc., for damp proof course at ground level below basement as per circular orders ..	S.ft.	0 5 0	1,634	
6	Laying burnt stone slabs 6″ thick one line dressed at top and 2 lines at exposed surfaces including fixing in mortar, etc., complete	,,	0 6 0	1,707	
7	Laying burnt stone slabs 6″ thick 2 lines dressed, the exposed faces including fixing in mortar, etc., complete	,,	0 8 0	305	
8	Pillars of stone masonry in mortar $1\frac{1}{2}'$ square in section with base and capital as per drawing at all sides pointing with cut lines, etc., complete	Each	20 0 0	18	
9	Providing and fixing teak-wood window fully glazed with shutters $1\frac{1}{4}''$ thick, frame, $3\frac{1}{2}' \times 5'$ with iron fittings bolts, hinges, etc., comeplet including $\frac{3}{4}''$ iron bars	S.ft.	1 8 0	717	
10	Providing and fixing teak-wood doors $\frac{1}{3}$ pannelled and $\frac{2}{3}$ glazed with shutters $1\frac{1}{2}''$ thick, frame $4' \times 5'$ with iron fittings, bolts, hinges, etc., complete	S.ft.	1 12 0	532	

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
11	Roofing of reinforced concrete interspaced with good ordinary brick (as per sketch) span about 11′ and designed to carry a super imposed load of 80 lbs. per square foot covered at top by 3″ of Surki concrete and 2 courses of flat tiles with ½″ smooth special lime mortar ceiling plaster at bottom, etc., complete	Sqr.	85 0 0	24.01	
12	Roofing details same as per item No. 11 except the span is about 7′	,,	80 0 0	18.99	
13	Tata's tested rolled steel I beams with one coat of red oxide paint including supplying, hoisting and fixing, etc., complete ..	Cwts.	10 0 0	103½	
14	Wire cut bricks in 1 : 2 lime mortar partition wall with ¾″ expanded metal in every 3 courses well bonded at either side into the walls, etc., complete	C.ft.	0 10 6	73	
15	Flooring 9″ boulder and sand filling at bottom and over that 3″ lime concrete and over that 1½″ cement concrete finished with smooth cement mixed with red ochre plaster rounding off at corners including joints, etc., complete	Sqrs.	25 0 0	34.80	
16	Parapet wall of stone masonry with stone balusters over windows as shown 2′ high 1¼′ thick with base and top cornice as per drawing including one line dressing, Quoins dressing, etc., complete	R.ft.	1 8 0	415	
17	Plain cornice 9″ thick single beading same as above	,,	0 8 0	402	
18	Chajja cornice above the entrance ..	,,	1 4 0	16	
19	Cement pointing with cut lines for size stone work in basement and superstructure of the exterior walls	Sqr.	3 4 0	41.24	
20	Plastering with lime mortar over stone wall ..	,,	4 0 0	24.50	
21	One line dressing of masonry in superstructure wherever necessary	S.ft.	0 2 0	3,190	
22	Plastering with lime mortar over brick walls .	Sqrs.	3 4 0	69.18	
23	White washing 2 coats	,,	0 4 0	93.68	
24	Painting rolled steel beams with 2 coats of green paint	,,	3 8 0	6.38	
25	Painting teakwood windows and doors with 2 coats of silicate paint	,,	3 8 0	17.81	
26	Boxing double girders with slab and brick in mortar wiring and plastering, etc., complete	R.ft.	0 8 0	141	
27	Coping for the compound wall as per drawing	,,	0 8 0	30	
28	Prov ding and fixing a collapsible gate ..	S.ft.	2 4 0	80	
29	Providing and fixing an ordinary gate for the compound	,,	1 0 0	35	
30	Down-water pipes	R.ft.	..	..	
	Constructing the Hos'el attached to the Urdu Middle School.				
1	Earthwork excavation for foundations keeping them at a side, filling in the sides of the excavat on and between the basement , watering, tamping, etc., complete ..	C.yd.	0 4 0	231	

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
2	Laying burnt granite stone jelly concrete in 1 : 2 lime and sand mortar including tamping etc., complete	C.ft.	0 3 6	1,577	
3	Constructing the foundation and basement with size stone in (1 : 2) lime and sand mortar	,,	0 5 0	3,694	
4	Constructing the superstructure with burnt brick in 1 : 2 lime mortar	,,	0 5 0	6,618	
5	Laying burnt stone slabs 6″ thick roughly dressed including filling in mortar in bed and asphalt joints on sides for damp proof courses at ground level	S.ft.	0 5 0	985	
6	Laying burnt stone slabs 6″ thick one line dressed at top and 2 lines at exposed surfaces including fixing in mortar, etc., complete	,,	0 6 0	1,301	
7	Wire cut bricks partition walls in 1 : 2 lime mortar with $\frac{3}{4}$″ expanded metal in every 3 courses well bonded on either side into the walls, etc., complete	C.ft.	0 10 6	368	
8	Providing and fixing teakwood doors fully panelled frame $3\frac{1}{2}$″×5″ thick with bolts, hinges of iron, etc., complete	S.ft.	1 12 0	324	
9	Providing and fixing teakwood windows with glazed shutters inside and panelled outside frame $3\frac{1}{2}$″×5″ with $\frac{3}{4}$″ iron bars, etc., complete	,,	2 8 0	324	
10	Providing cement perforated ventilators and panels including fixing	,,	1 8 0	204	
11	Panel moulding below the cement perforated windows as per drawing	,,	0 4 0	24	
12	Tata's rolled steel I beams with one coat of red oxide paint including supplying, hoisting, fixing, etc., complete	cwt.	10 0 0	$66\frac{1}{2}$	
13	Roofing of reinforced concrete interspaced with good ordinary bricks as per sketch, span about 8′ designed to carry a superimposed load of 80 lbs. per sq. ft. covered at top by 3″ of surki concrete and 2 courses of flat tiles with $\frac{1}{2}$″ smooth plaster finished to necessary slopes and special lime mortar ceiling plaster at bottom, etc., complete ..	Sqrs.	80 0 0	29.57	
14	Flooring :—9″ boulder and sand filling at bottom and over that 3″ lime concrete and over that $1\frac{1}{2}$″ cement concrete and over that $1\frac{1}{2}$″ cement concrete finished with red ochre plaster including joints, etc., complete	Sqrs.	25 0 0	25.25	
15	Parapet wall with mouldings over windows as shown $2\frac{1}{4}$′ high $\frac{3}{4}$″ thick including plastering, base and top cornice, etc., complete..	R.ft.	1 8 0	233	
16	Cornice 9″ thick with stanchions as shown in the drawing, same as above	,,	0 9 0	233	
17	Chajja cornice in front	,,	1 4 0	12	
18	Cement pointing with cut lines for size stone work in basement	Sqrs.	3 4 0	4.66	
19	Plastering with lime mortar over brick walls with lime plaster	,,	3 4 0	120.22	
20	Colour washing outside, 2 coats	,,	0 5 0	27.00	
21	White washing inside, 2 coats	,,	0 4 0	93.22	

No.	Items of work	Per	Rate	Quantity	Rate to be quoted
			Rs. a. p.		
22	Painting teakwood windows and doors with 2 coats of silicate paint	,,	3 8 0	17.82	
23	Painting rolled steel beams with 2 coats of green paint	,,	3 8 0	8.53	
24	Providing and fixing a collapsible gate in front	S.ft.	2 4 0	58	
25	Down water pipes	R.ft.	..	..	

N. KRISHNIENGAR,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification, dated 4th February 1936.

The attention of the public is invited to the notification on pages 214-215 of the issue of the *Mysore Gazette*, dated 13th February 1936, inviting tenders for the work of restoring Gollahalli Ayyavarakere, Register No. 518 of Bagepalli Taluk.

The last date fixed for the receipt of the tender in this office is 2 P.M. on 28th February 1936.

Abstract Notification, dated 6th February 1936.

The attention of the public is invited to the notification on pages 215-218 of the issue of the *Mysore Gazette*, dated 13th February 1936, calling for tenders for closing the breach and extending left waste weir of Thimmampalli Nayankere, Register No. 859 of Bagepalli Taluk.

The last date fixed for the receipt of tenders is 2 P.M. on 24th March 1936.

Notification, dated 17th February 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 16th March 1936, for improvements to the feeder channel of Bodimarlur, Register No. 164, Goribidnur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of October 1936.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M. of office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees Two Hundred in cash or Government Promissory Notes, as earnest money, and be superscribed 'Tender for improvements to the feeder channel of Bodimarlur Tank, Register No. 164, Goribidnur Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.